



तुलसीपुर उपमहानगरपालिका
नगर कार्यपालिकाको कार्यालय



पत्र संख्या:
च.न.

तुलसीपुर, दाङ
लुम्बिनी प्रदेश, नेपाल
तुलसीपुर उपमहानगरपालिका
नगर कार्यपालिकाको कार्यालय
तुलसीपुर, दाङ
लुम्बिनी प्रदेश, नेपाल
२०७३

दररेट पेश गर्ने सम्बन्धि सुचना।
प्रथम पटक सुचना प्रकाशित मिति: २०८१-०२-२५ गते

यस तुलसीपुर उपमहानगरपालिका द्वारा विभिन्न फर्म संग तपशिल बमोजिमको कार्य गर्नका लागि शिलबन्दी दररेट पेश गर्ने यो सुचना प्रकाशित गरिएको छ।

| क्र.स | कामको विवरण | जम्मा रकम (मु.अ.क.सहित) | दररेट पेश गर्ने अन्तिम मिति | कैफियत |
|-------|----------------------------------------------------------------------------------------------------------------|----------------------------|----------------------------------|--------|
| १ | वडा न: १६ को आचार्यकुलमन्दिर देखि पश्चिम क्रसरजाने वाटोमा पक्की नाला र दुङ्गाको बाल निर्माण गर्ने काम | ४६९१७३।२८ | २०८१-०२-३१ कार्यालय समय भित्र | |

-दररेट पेश गर्ने फर्मले अनिवार्य रूपमा दररेट पेश गर्ने ब्यहोराको लिखित निवेदन सहित नविकरण भएको फर्म दर्ता प्रमाणपत्रको प्रतिलिपी र आर्थिक वर्ष २०७९/०८० को करचुक्ता प्रमाणपत्रको प्रतिलिपी पेश गर्नु पर्ने छ।

-दररेट पेश गर्ने फर्म तुलसीपुर उपमहानगरपालिका कार्यालयमा सुचिकृत हुनुपर्ने छ।

-उक्त कार्यका लागि आवश्यक BOQ तुलसीपुर उपमहानगरपालिकाको वेवसाइट <http://www.tulsipurmun.gov.np> बाट डाउनलोड गर्न सकिने छ।

-BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पस्ट बुझिने गरि लेखेर पेश गर्नु पर्ने छ। केरमेट भएको दररेट मुल्यांकनमा समावेश गरिने छैन।

(प्रमुख प्रशासकीय अधिकृत)

गेहेन्द्र बहादुर डाँगी
प्रमुख प्रशासकीय अधिकृत

Tulsipur Submetropolitan City
Office of the Municipal Executive
Lumbini Province, Dang
Tulsipur, Nepal

BOO
 पुल्सीपुर, दण्डा
 २०७३

Name of Project: Acharya kul mandir dekhi pashim krasar jane bato ma prakhal nirman.
 Location : Tulsipur sub-metropolitan city -16, Dang.

गोविन्द बहादुर ङांगी
 प्रमुख प्रशासकीय अधिकृत

| S.N | Description | Unit | Quantity | In Fig. | Rate | | Amount | Remarks |
|-----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|---------|-----------|--|--------|---------|
| | | | | | In word's | | | |
| 1 | Information board. | Ls | 1.00 | | | | | |
| 2 | Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means) | Cu.m | 28.94 | | | | | |
| 3 | Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (Old Norms) | Cu.m | 3.49 | | | | | |
| 4 | Providing and laying of PCC (Grade M 10) in foundation complete as per Drawing and Technical Specifications | Cu.m | 2.40 | | | | | |
| 5 | Providing and laying Random Rubble Stone Masonry work in cement mortar 1:4 in structure including pointing works and providing necessary 100 mm dia HDPE pipes for weep holes etc all complete as per Drawing and Technical Specifications | Cu.m | 39.60 | | | | | |
| | Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications including form works all complete. (2000) | Cu.m | 2.36 | | | | | |
| | Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS Clause 2014) | Kg | 95.94 | | | | | |
| | Total | | | | | | | |
| | VAT 13% | | | | | | | |
| | Grand total. | | | | | | | |