



तुलसीपुर उपमहानगरपालिका  
नगरकार्यपालिकाको कार्यालय,



सार्वजनिक निर्माण कार्यका दररेट पेश गर्ने सम्बन्धी सूचना

(प्रथम पटक प्रकाशित मिति: २०८१।०४।२०)

१) यस उपमहानगरपालिकाको वार्षिक स्वीकृत कार्यक्रम अन्तर्गत तपशिल बमोजिमले सार्वजनिक निर्माण कार्य गर्नु पर्ने भएकाले सूचिकृत, इच्छुक र इजाजत प्राप्त फर्म/कम्पनी/संस्थाले देहाय बमोजिमको शर्तहरूको अधिनमा रही रितपूर्वकको स्मिथिकीकेशन सहित दररेट पेश गर्नुहुन यो सूचना प्रकाशित गरिएको छ।

आयोजनाको नाम	ढेका प्रक्रिया	लागत अनुमान - मु अ कर र पि.स बाहेक)	दररेट पेश गर्ने अन्तिम मिति
पालिका अगाडि पर्खाल निर्माण	Direct Quotation (सोभै खरिद)	₹००८९४।०७	August 11 2024(2081/04/27) at 5.00 PM

- २) दररेट पेश गर्ने दाताहरूले थप जानकारी र BOQ तुलसीपुरउपमहानगरपालिका को website: [www.tulsipurmun.gov.np](http://www.tulsipurmun.gov.np) तथा तुलसीपुर उपमहानगरपालिका नगरकार्यपालिकाको कार्यालयबाट लिन सम्झनुने छ।
- ३) अन्य कार्यविधिहरू सार्वजनिक खरिद ऐन, २०६३ सार्वजनिक खरिद नियमावली, २०६४ (संशोधन सहित) तथा नेपाल सरकारका अन्य प्रचलित कानून बमोजिम हुनेछन्।

  
सिनेश भुषा  
सहायक प्रशासकीय अधिकृत  
नगर कार्यपालिका  
तुलसीपुर

नेहेन्द्र बहादुर डाँगी  
प्रमुख प्रशासकीय अधिकृत



Tulsipur Sub-Metropolitan City  
Office Of The Municipal Executive

Tulsipur Sub-Metropolitan City  
Lumbini Province, Nepal  
B.O.G. (Municipal Executive)  
Tulsipur, Dang  
Lumbini Province, Nepal  
2073



Name Of Project:- Construction Of Boundary Wall In Front Of Sub-Metropolitan Office  
Location:- Tulsipur-05,Dang

नेहेन्द्र शिवाजी  
नगर प्रशासकीय अधिकृत

SN	Particulars	Unit	Quantity	Rate In Nrs.		Amount (NRP)	Remarks
				In Figure	In Words		
A	Provisional Sum						
	Lab Test	Ps	1.00	20,000.00			
B	Civil Works						
1	Cutting and unrooting of grasses, Cutting or filling of top soil upto 0.15m, cutting and levelling of construction site by cutting of soil hips, filling of pits and ditches and clearing of all the organic materials from construction Site as per instruction of Engineer	Sq.m	160.00				
2	Earthwork in excavation in trenches, foundation/raft foundation etc. in soil by manpower including dressing of sides, ramming of bottom, dewatering, shoring/Shuttering, if necessary, lift up to 5 m, stacking of excavated materials at least 4m clear from the edge of excavation within a lead of 10m as per drawings and Instruction of Engineer	cum	19.08				
3	Providing and laying uncoursed hand packed Dry Rubble Stone soling in foundation, floors of building, retaining wall, steps and ramps with out any special dressing of stone including filling interstices with suitable quarry waste or stone chips or quarry sand, watering, compacting using appropriate mechanical compaction means with all contractors materials, handling, placing etc. all complete as per drawings, specifications and instruction of the Engineer. The complete item including all lead & lift.	cum	3.87				
4	Supplying, mixing, placing, compaction and curing Plain Cement Concrete (1:2:4) in foundation bases, Floors etc. as per drawing, specification and instruction of Engineer	cum	2.58				
5	Providing and laying random rubble stone masonry work in ratio 1:4 cement sand mortar in foundation complete as per Drawing and Technical Specifications.	cum	7.28				
6	RCC, Supplying, mixing, placing, compact and cure machine mixed concrete in foundation footings, tie-beams, columns and Sill/liniels, as per drawings, specification and approval of engineer. Concrete mix - 1:1.5:3 for RCC work	cum	6.32				
7	Providing and laying brick masonry using first class chimney burnt bricks, with cement and sand mortar 1:4 including scaffolding, curing, filling, cleaning and racking out mortar joints, making ducts, recesses where required including all materials, labor, lead and lift as per drawing, specification and approval of engineer	cum	11.85				
8	12.5 mm thick cement sand plaster work (1:4) on wall including supply of materials, labor, mixing, levelling, curing & scaffolding etc. all complete as per drawing, specification and approval of engineer.	Sq.m	105.72				



Tulsipur Sub-Metropolitan City  
Office Of The Municipal Executive

Tulsipur, Dang  
Lumbini Province, Nepal  
BOO (Bidding Activity)

Tulsipur Sub-Metropolitan City  
Office of the Municipal Executive  
Tulsipur, Dang  
Lumbini Province, Nepal  
2073

नेहेन्द्र बहादुर राणा  
नगरपालिका अध्यक्ष

Name Of Project:- Construction Of Boundary Wall In Front Of Sub-Metropolitan Office  
Location:- Tulsipur-05,Dang

SN	Particulars	Unit	Quantity	Rate		Amount (NRP)	Remarks
				In Figure	In Words		
9	Providing and Applying Primer coat and two coats of the approved brand, color & quality silicon based weather coat 1st quality emission for exterior wall paint (Nerolac, Burger, Asian Paints, Brita or equivalent) to achieve evenly shaded surface including the cost of scaffolding as per the specifications & instructions all complete.	Sq.m	105.72				
10	Supply, fabrication and fixing in position of MS Grills for Windows opening at Ground Floor, 10mm*10mm Solid Core Square Rod welded on 4.5mm*20mm MS Strip Frame, Horizontal Spacing of Square Rod should be 75mm c/c and the rod should be so spaced horizontally that its pair of spacing 75mm should have maximum 300mm clear spacing with each pair with primer Paint all complete and as per the approval of Site Engineer	Sq.m	12.60				
11	Providing and application of two or more coats paint with synthetic enamel paint of approved brand and color to give an even and uniform shade all complete	Sq.m	7.00				
12	Providing, placing, fixing, centering and shuttering of plywood or steel formwork in any shape and sizes for slabs, beams, columns, shear walls, Lintel, foundation etc including nails, propping supports and removal of the same at any leads and lifts all complete as per drawing, specification and instruction of Engineer	Sq.m	47.70				
13	Supplying, cutting, bending, placing in position and binding TMT reinforcement bars of all sizes with provision of cover block of cement mortar (1:1), providing and fixing chairs, spacers to keep the bars in intended position including the cost of 18 gauge black iron binding wire all complete as per drawing and specification	Kg	579.32				
14	HDPPE Pipe PNI(20mm Min Outer Dia)	Rm	100.00				
			<b>Sub Total</b>				
			<b>13 % VAT</b>				
			<b>Grand Total</b>				

Firm Name:-  
Address:-  
Authorized Signature:-  
Firm Seal:-